



Bonneagar Iompair Éireann  
Transport Infrastructure Ireland

## TII Publications

GE PE DN CC OP AM RE

---

# Notes for Guidance on the Specification for Road Works Series NG 2300 - Bridge Expansion Joints and Sealing of Gaps

**CC-GSW-02300**

December 2010

## About TII

Transport Infrastructure Ireland (TII) is responsible for managing and improving the country's national road and light rail networks.

## About TII Publications

TII maintains an online suite of technical publications, which is managed through the TII Publications website. The contents of TII Publications is clearly split into 'Standards' and 'Technical' documentation. All documentation for implementation on TII schemes is collectively referred to as TII Publications (Standards), and all other documentation within the system is collectively referred to as TII Publications (Technical). This system replaces the NRA Design Manual for Roads and Bridges (NRA DMRB) and the NRA Manual of Contract Documents for Road Works (NRA MCDRW).

## Document Attributes

Each document within TII Publications has a range of attributes associated with it, which allows for efficient access and retrieval of the document from the website. These attributes are also contained on the inside cover of each current document, for reference. For migration of documents from the NRA and RPA to the new system, each current document was assigned with new outer front and rear covers. Apart from the covers, and inside cover pages, the documents contain the same information as previously within the NRA or RPA systems, including historical references such as those contained within NRA DMRB and NRA MCDRW.

## Document Attributes

<b>TII Publication Title</b>	<i>Notes for Guidance on the Specification for Road Works Series NG 2300 - Bridge Expansion Joints and Sealing of Gaps</i>
<b>TII Publication Number</b>	<i>CC-GSW-02300</i>

<b>Activity</b>	<i>Construction &amp; Commissioning (CC)</i>
<b>Stream</b>	<i>Guidance on Specification for Works (GSW)</i>
<b>Document Number</b>	<i>02300</i>

<b>Document Set</b>	<i>Standards</i>
<b>Publication Date</b>	<i>December 2010</i>
<b>Historical Reference</b>	<i>Series NG 2300</i>

## NRA DMRB and MCDRW References

For all documents that existed within the NRA DMRB or the NRA MCDRW prior to the launch of TII Publications, the NRA document reference used previously is listed above under 'historical reference'. The TII Publication Number also shown above now supersedes this historical reference. All historical references within this document are deemed to be replaced by the TII Publication Number. For the equivalent TII Publication Number for all other historical references contained within this document, please refer to the TII Publications website.

---

# ***BRIDGE EXPANSION JOINTS AND SEALING OF GAPS***

## ***Contents***

---

<b><i>Clause</i></b>	<b><i>Title</i></b>	<b><i>Page</i></b>
NG 2301	General.....	2
NG 2302	Installation of Bridge Deck Expansion Joints .....	2
NG 2303	In Situ Nosings .....	2
NG	Sample Appendices.....	3

# Bridge Expansion Joints And Sealing Of Gaps

## NG 2301 General

- 1 A schedule of expansion joints should be included in Appendix 23/1, cross referring to the drawings in the Contract where appropriate. Where the use of proprietary joints or materials is envisaged, or the joint is not fully detailed on the drawings in the Contract, Appendix 23/1 should also give details of the design movements, to enable the Contractor to propose appropriate joints. Particular requirements for subsurface drainage should be described in Appendix 23/1, cross-referring to the drawings in the Contract where appropriate.
- 2 The Employer's Representative should check that all bridge deck expansion joints proposed by the Contractor for use in the Works have a current NSAI Agrément Certificate, or equivalent.
- 3 Where gap sealing is required, e.g. between wing walls and abutments, the details should be shown on the drawings in the Contract, with cross references to them and a schedule, if applicable, in Appendix 23/2.

## NG 2302 Installation of Bridge Deck Expansion Joints

- 1 The installation of expansion joints requires a very high standard of workmanship and supervision if premature failure is to be avoided.
- 2 The width of the expansion joint gap and, where appropriate, the deck joint gap to be provided should be related to the amount of residual creep, shrinkage, structural rotation and temperature movements that may be expected in the deck and to the prevailing deck temperature at the time of setting the joint gap. Where a preformed compression seal is to be incorporated in the gap, the gap setting should ensure that the seal does not lock up

solid before full expansion has taken place.

- 3 Hardboard has proved to be effective in preventing surfacing materials, where they are to be cut back, adhering to the deck or the waterproofing.
- 4 Holding down bolts installed at an early stage of the deck construction are particularly vulnerable to damage. Care should be taken to protect threads from damage as any slight imperfections may prevent the pre-determined torque load being achieved.
- 5 Where constituent parts of a joint system are required to be cured, the manufacturer's advice should be considered in conjunction with the actual mean air temperature when determining the curing time before the joint can be trafficked.
- 6 Specific requirements for the protection of newly installed joints should be shown on the drawings in the Contract, where appropriate.

## NG 2303 In Situ Nosings

- 1 Nosings should be dimensioned on the drawings in the Contract. They should only be applied to sound concrete and it is imperative that concrete affected by cracking or deterioration be replaced.
- 2 It is emphasised that satisfactory in situ resin based mixes can only be achieved with completely dry aggregates.
- 3 Resin based materials of any composition when placed in thin layers, say 12 mm thick, may not generate sufficient heat to cure satisfactorily below 10°C. A temperature of 10°C or above may be obtained by means of artificial heating to a constant temperature over the whole area.

## NG Sample Appendices

### NG SAMPLE APPENDIX 23/1: BRIDGE DECK EXPANSION JOINT SCHEDULE

All bridge deck expansion joints shall satisfy the requirements of NRA Addendum to BD 33 'Expansion Joints for Use in Highway Bridge Decks'.

*[Notes to compiler: This schedule should list all bridge expansion joints in the Contract by type as described in Table 1 of BD 33/94 and give a cross-reference to the drawing number where the joint location is shown. The movement fringes of each joint should be given to enable the Contractor to propose an appropriate joint. Particular requirements for subsurface drainage, including the position and invert level of connections to surface water drains or soakaways should be given. Requirements for surface preparation and protection of metal components against corrosion should also be given.]*

### NG SAMPLE APPENDIX 23/2: SEALING OF GAPS SCHEDULE (OTHER THAN IN BRIDGE DECK EXPANSION JOINTS)

*[Note to compiler: This schedule should include all gap sealing such as joints between wing wall and abutment, etc. Typical aspects to be included are:]*

- (i) Joint types and references
- (ii) Filler requirements
- (iii) Sealant requirements
- (iv) Water stop requirements
- (v) A cross-reference to the drawing number giving this or further information.



Bonneagar Iompair Éireann  
Transport Infrastructure Ireland



Ionad Ghnó Gheata na  
Páirce,

Stráid Gheata na Páirce,  
Baile Átha Cliath 8, Éire



[www.tii.ie](http://www.tii.ie)



+353 (01) 646 3600



Parkgate Business Centre,  
Parkgate Street,  
Dublin 8, Ireland



[info@tii.ie](mailto:info@tii.ie)



+353 (01) 646 3601