

MANUAL OF CONTRACT DOCUMENTS FOR ROAD WORKS: VOLUME 3
SECTION 1: METHOD OF MEASUREMENT FOR ROAD WORKS

Contents

CHAPTER I Definitions

CHAPTER II General Principles

CHAPTER III Preparation of Bill of Quantities

Preambles to Bill of Quantities

CHAPTER IV Units and Method of Measurement

Series 100 Preliminaries

Definitions

Temporary Accommodation

Permanent Accommodation

Vehicles for the Employer's Personnel

Communication System for the Employer's Personnel

Operatives for the Employer's Representative

Information Board

Traffic Safety and Management

Temporary Diversion for Traffic

Recovery Vehicles

Progress Photographs

Road Sweeping and Cleaning

Emergency Services

Facilities for Local Authority, Public or Private Utility Undertakers
and Other Contractors

Property Condition Surveys

Series 200 Site Clearance

Site Clearance

Take Up or Down and Set Aside for Re-use or Remove to Store Off Site

Series 300 Fencing and Environmental Noise Barriers

Fencing, Gates and Stiles

Remove from Store and Re-erect Fencing Gates and Stiles

Walls and Environmental Noise Barriers

Series 400 Safety Barriers and Pedestrian Guardrails

Definition

Safety Barrier System

Terminals

Delivery of Materials and Equipment for Maintenance Purposes

Temporary Safety Barriers

Pedestrian Guardrails and Handrails

Anti-Glare Screens

Series 500 Drainage and Service Ducts

Definitions

Drains, Sewers, Piped Culverts and Service Ducts (excluding Filter Drains,
Narrow Filter Drains & Fin Drains)

Filter Drains

Fin Drains and Narrow Filter Drains

Connections

Chambers and Gullies

Headwalls and Outfall Works

Small Headwalls

Soft Spots and Other Voids

Supports Left in Excavation

Drainage and Service Ducts in Structures (including Reinforced Earth
Structures and Anchored Earth Structures)

Filling to Pipe Bays and Verges on Bridges

Renewal, Raising or Lowering Covers and Gratings on Existing Chambers
and Gullies

Remove from Store and Reinstall Chamber Covers and Gully Gratings and
Frames

Grouting up of Existing Drains, Sewers, Piped Culverts and Service Ducts

Excavation in Hard Material

Backdrop Chambers

Series 600 Earthworks

Definitions and Measurement General

Excavation

Excavation in Hard Material

Processing of Unacceptable Material Class U1

Deposition of Fill

Disposal of Material

Imported Fill
Compaction of Fill
Geotextiles
Soft Spots and Other Voids
Disused Sewers, Drains, Cables, Ducts, Pipelines and the Like Occurring
at Formation or Sub-formation Level; Disused Basements,
Cellars and the Like and Gullies
Supports Left in Excavation
Topsoiling and Storage of Topsoil
Grass Seeding and Turfing
Completion of Formation and Sub-formation
Lining of Watercourses
Clearing of Existing Ditches
Ground Improvement – Establishment of Dynamic Compaction Plant
Ground Improvement – Dynamic Compaction
Gabion Walling and Mattresses
Crib Walling
Filling and Caps to Mine Working, Well, Swallow Hole and the Like
Ground Anchorages – Ground Anchorage Plant
Ground Anchorages
Ground Anchorages – Waterproofing Anchorage Boreholes
Instrumentation and Monitoring – Boring Plant
Instrumentation and Monitoring – Boring Holes
Instrumentation and Monitoring – Instrumentation
Instrumentation and Monitoring – Instrument Hut or Cabinet
Instrumentation and Monitoring – Monitoring Equipment
Ground Water Lowering
Trial Pits
Breaking Up and Perforation of Redundant Pavement
Perforation of Redundant Slabs, Basements and the Like

Series 700 Pavements
Sub-base
Pavement
Regulating Course
Surface Treatment
Tack Coat
Cold Milling (Planing)
Reinstatement of Paved Areas

Repairs to Existing Concrete Carriageway

Series 800 *Not taken up*

Series 900 *Not taken up*

Series 1000 *Not taken up*

Series 1100 **Kerbs, Footways and Paved Areas**

Kerbs, Channels, Edgings and Combined Drainage and Kerb Blocks

Additional Concrete for Kerbs, Channels,
Edgings and Combined Drainage and Kerb Blocks

Remove from Store and Relay Kerbs, Channels, Edgings and
Combined Drainage and Kerb Blocks

Footways and Paved Areas

Remove from Store and Relay Paving Flags and Blocks

Steps

Series 1200 **Traffic Signs and Road Markings**

Traffic Signs

Remove from Store and Re-erect Traffic Signs

Road Markings

Retroreflecting Road Studs

Remove from Store and Re-install Retroreflecting Road Studs

Traffic Signals Installations

Pedestrian Crossings

Permanent Bollards

Node Markers

Reflective Markers

Series 1300 **Road Lighting Columns and Brackets**

Road Lighting Columns, Brackets and Wall Mountings

Remove from Store and Re-erect Road Lighting Columns,
Brackets and Wall Mountings

Series 1400 **Electrical Work for Road Lighting and Traffic Signs**

Locating Buried Road Lighting and Traffic Signs Cable

Cabling

Cable Joints and Terminations

Feeder Pillars

Earth Electrodes

Series 1500 **Motorway Communications**

Locating Buried Communications Cable

Communications Cabling
Communications Cable Joints and Terminations
Communications Equipment
Remove from Store and Re-install Communications Cabling and Equipment
Loop Detector Installations
Site Records
Stage 2 Commissioning of Cable

Series 1600 Piling and Embedded Retaining Walls

Piling Plant
Precast Concrete Piles
Cast-in-place Piles
Reinforcement for Cast-in-place Piles
Steel Bearing Piles
Proof Loading of Piles
Steel Sheet Piles
Embedded Retaining Wall Plant
Diaphragm Walls
Secant Pile Walls
Contiguous Bored Pile Walls
Reinforcement for Embedded Retaining Walls
King Post Wall Plant
King Posts
Reinforcement for King Post Piles
King Post Walling

Series 1700 Structural Concrete

In Situ Concrete
Precast Concrete
Surface Finish of Concrete – Formwork
Surface Finish of Concrete – Patterned Profile Formwork
Steel Reinforcement for Structures
Reinforcement for Reinforced and Anchored Earth Structures
In Situ Post-tensioned Prestressing for Structures

Series 1800 Steelwork for Structures

Fabrication and Erection of Steelwork
Fabrication of Steelwork
Erection of Steelwork
Miscellaneous Metalwork
Corrugated Steel Buried Structures

	Metal Facing Units for Reinforced Earth Structures
Series 1900	Protection of Steelwork Against Corrosion Protective System
Series 2000	Waterproofing for Structures Waterproofing Surface Impregnation and Coatings of Concrete Removal of Existing Waterproofing
Series 2100	Bridge Bearings Bearings
Series 2200	Parapets Parapets
Series 2300	Bridge Expansion Joints and Sealing of Gaps Bridge Deck Expansion Joints Sealing of Gaps
Series 2400	Brickwork, Blockwork and Stonework Brickwork Blockwork and Stonework Remove from Store and Relay Brickwork, Blockwork and Stonework
Series 2500	Structures Designed by the Contractor Structures Designed by the Contractor
Series 2600	Not taken up
Series 2700	Watermains, Utilities and Accommodation Works Watermains Connections Pipe Fittings Valves and Penstocks Chambers Thrust Blocks
Series 2800	Trenchless Installation of Road Drainage & Service Ducts Scope Definitions Establishment and Removal of Plant Drain and Service Ducts Lateral Connections to Pipes to be Replaced by On-line Replacement

Series 2900	CCTV Survey of Road Drainage Systems
	Scope
	CCTV Survey of Highway Drainage Systems