

Series 1600: Piling and Diaphragm Walling

1 Casings and Linings

Casings and linings are to be regarded as temporary unless the Contract states specifically that they are to be left in place.

2 Steel Bearing Piles

If it is anticipated that the final lengths of the steel bearing piles may differ from those originally required in the Contract then items for lengthening or shortening should be included. In the case of cutting or burning off surplus, the number admeasured should be of those piles reaching a set at a length shorter than originally required and accepted by the Engineer. The item for cutting or burning off surplus piles applies to both steel bearing piles and lengthened steel bearing piles.

3 Diaphragm Walls

Where a diaphragm wall is required to have a special finish the item coverage in paragraph 65 of Series 1600 will need to be expanded.

