



Bonneagar Iompair Éireann
Transport Infrastructure Ireland

TII Publications



Requirements for Measuring and Pricing of Trenchless Installation of Road Drainage and Service Ducts

CC-RMP-02800
January 2019

About TII

Transport Infrastructure Ireland (TII) is responsible for managing and improving the country's national road and light rail networks.

About TII Publications

TII maintains an online suite of technical publications, which is managed through the TII Publications website. The contents of TII Publications is clearly split into 'Standards' and 'Technical' documentation. All documentation for implementation on TII schemes is collectively referred to as TII Publications (Standards), and all other documentation within the system is collectively referred to as TII Publications (Technical).

Document Attributes

Each document within TII Publications has a range of attributes associated with it, which allows for efficient access and retrieval of the document from the website. These attributes are also contained on the inside cover of each current document, for reference.

TII Publication Title	<i>Requirements for Measuring and Pricing of Trenchless Installation of Road Drainage and Service Ducts</i>
TII Publication Number	CC-RMP-02800

Activity	<i>Construction & Commissioning (CC)</i>	Document Set	<i>Select Document Set</i>
Stream	<i>Requirements for Measuring and Pricing (RMP)</i>	Publication Date	<i>January 2019</i>
Document Number	<i>02800</i>	Historical Reference	Series MM 2800

TII Publications Website

This document is part of the TII publications system all of which is available free of charge at <http://www.tiipublications.ie>. For more information on the TII Publications system or to access further TII Publications documentation, please refer to the TII Publications website.

TII Authorisation and Contact Details

This document has been authorised by the Director of Professional Services, Transport Infrastructure Ireland. For any further guidance on the TII Publications system, please contact the following:

Contact: Standards and Research Section, Transport Infrastructure Ireland
 Postal Address: Parkgate Business Centre, Parkgate Street, Dublin 8, D08 DK10
 Telephone: +353 1 646 3600
 Email: infoPUBS@tii.ie

TII Publications



Activity:	Construction & Commissioning (CC)
Stream:	Requirements for Measuring and Pricing (RMP)
TII Publication Title:	Requirements for Measuring and Pricing of Trenchless Installation of Road Drainage and Service Ducts
TII Publication Number:	CC-RMP-02800
Publication Date:	January 2019
Set:	Select Document Set

Contents

1. Trenchless Installation of Road Drainage & Service Ducts.....	1
2. References.....	5

**Updates to TII Publications resulting in changes to
Requirements for Measuring and Pricing of Trenchless Installation of Road Drainage and
Service Ducts CC-RMP-02800**

Date: January 2019

Page No: 3

Section No: 12

Amendment Details:

Minor referencing error amended.

Contents Table

1.	Trenchless Installation of Road Drainage & Service Ducts.....	1
2.	References.....	5
2.1	TII Publications (Standards) References	5

1. Trenchless Installation of Road Drainage & Service Ducts

- Scope**
- 1 This document applies to the installation by trenchless techniques of road drains, service ducts, sleeves and culverts of internal diameters 900mm or less. The method of installation will be selected by the Tenderer to meet the requirements of Appendix 28/1 of the Specification document.
- 2 This document covers the Trenchless or Minimum Dig installation and the associated Temporary Works. All other items of permanent works shall be measured under CC-RMP-00500. For purposes of this measurement the launch and reception pits are considered Temporary Works.
- Definitions**
- 3 Where the ground level has been subjected to treatment, under the Contract, in respect of ground improvement, mine workings, swallow holes and the like, for the purposes of Trenchless Techniques, Existing Ground level shall be the level of the ground before any work under the contract has been carried out.

Establishment and Removal of Plant

- Units**
- 4 The units of measurement for establishment and removal of plant shall be:
- (i) establishment and removal of plant.....item.

- Measurement**
- 5 The establishment and removal of plant shall be measured once only to each pipe run. Any additional establishment and removal to suit the Contractor's method of working shall not be measured.

- Itemisation**
- 6 Separate items shall be provided for plant in accordance with Section 3 of CC-RMP-00010, paragraphs 3 and 4 and the following:

Group	Feature
I	1 Pipe run reference
II	1 Establishment and removal of plant

- Establishment and Removal of Plant**
- 7 The items for the establishment of trenchless installation and plant shall in accordance with the Preambles to Bill of Quantities General Directions include for:

- Item Coverage**
- (a) bringing plant and equipment to the site of the pipe run;
- (b) setting up plant and equipment at each pipe run;
- (c) dismantling and removing plant and equipment on completion of the pipe run;
- (d) construction of launch and reception pits and all reinstatement;
- (e) thrust and winch blocks and their removal on completion of the pipe run;
- (f) site preparation and access arrangements;
- (g) lead-in trenches and their reinstatement;
- (h) ground stabilisation treatment;

- (i) dealing with existing flows;
- (j) construction and reinstatement of launch and reception eyes;
- (k) alteration and reinstatement of existing chambers used as launch and reception pits;
- (l) protection of existing or completed pipes in chambers;
- (m) replacing acceptable material rendered unacceptable;
- (n) taking precautions to avoid damage to property, structures, drains, services, pavements, instrumentation and the like, including monitoring;
- (o) excavation of acceptable material (CC-RMP-00600 paragraphs 17 and 18);
- (p) excavation of unacceptable material (CC-RMP-00600 paragraph 19);
- (q) excavation of hard material (CC-RMP-00600 paragraph 23);
- (r) excavation in contaminated land and disposal of all contaminated materials including clothing, wash water and any other materials to a licensed site;
- (s) disposal of material (CC-RMP-00600 paragraph 39);
- (t) establishment and supply of water.

Drain and service ducts

- Units** **8** The unit of measurement for pipe runs shall be:
- (i) pipe run reference linear metre.
- Measurement** **9** The measurement of a pipe run shall be the lengths measured along the centre line of the pipe between any of the following:
- (a) the internal faces of permanent chambers;
 - (b) the external faces of headwalls;
 - (c) the position of termination shown in the Contract.
- 10** The measurement of service ducts shall be for the complete construction irrespective of the number of ducts contained within any one bore. Where more than one duct is laid in a bore then the number of ducts shall be stated in the item description.
- Itemisation** **11** Separate items shall be included for each pipe run in accordance with Section 3 of CC-RMP-00010, paragraphs 3 and 4 and the following:

Group	Feature
I	1 Pipe run reference
II	1 Drain
	2 Service ducts
	3 Lining
III	1 New Installation
	2 On-line Replacement
	3 Minimum Dig
	4 Rehabilitation
IV	1 Internal diameter
V	1 Existing internal diameter (Rehabilitation only)

Drains and service ducts

12

The items for pipe runs shall in accordance with the Preambles to Bill of Quantities General Directions include for:

Item Coverage

- (a) excavation of acceptable material (CC-RMP-00600 paragraphs 17 and 18);
- (b) excavation of unacceptable material (CC-RMP-00600 paragraph 19);
- (c) excavation of hard material (CC-RMP-00600 paragraph 23);
- (d) supply and installation of pipes;
- (e) cutting and jointing of pipes and fittings, including packers;
- (f) building in pipes to chambers, headwalls and outfall works including reshaping inverts and benching;
- (g) disposal of material (CC-RMP-00600 paragraph 39);
- (h) cleaning, clearing obstructions and testing including all CCTV surveys and inspections;
- (i) recording, staking and labelling;
- (j) in the case of ducts, fixing draw ropes, removable stoppers, marker blocks and posts;
- (k) pipe schedules and records in accordance with Appendix 28/1;
- (l) measures for reduction of friction, including lubricants and their disposal;
- (m) protective system (CC-RMP-01900 paragraph 5);
- (n) sleeves;
- (o) support and drilling fluid and disposal;
- (p) surveys and monitoring in accordance with Appendix 28/1;
- (q) grouting including packers and fixings;
- (r) breakout and reinstatement of start and end headings at existing chambers;
- (s) ground stabilisation treatment;
- (t) dealing with existing flows;
- (u) cleaning existing sewers of debris, silt, obstructions and other material including disposal;
- (v) standing time waiting for deformed pipes to normalise;
- (w) taking precautions to avoid damage to property, structures, drains, services, pavements, instrumentation and the like, including monitoring;
- (x) excavation in contaminated land and disposal of all contaminated materials including clothing, wash water and any other materials to a licensed site;
- (y) photographs;
- (z) delivery of samples for testing.

Lateral connections to pipes to be replaced by on-line replacement

Units

13

The unit of measurement for lateral connections shall be:

- (i) lateral connection reference.... number.

- Measurement** **14** The depth of lateral connection shall be the vertical measurement between the invert of the lateral pipe and the Existing Ground Level except where the Earthworks Outline is below the Existing Ground Level the measurement shall be taken to the Earthworks Outline.
- Itemisation** **15** Separate items shall be included for lateral connections in accordance with the following:
- | Group | Feature |
|--------------|--|
| I | 1 Lateral connection reference |
| II | 1 Drain |
| | 2 Service ducts |
| III | 1 Different Internal Diameters of lateral pipes |
| IV | 1 Different Internal Diameters of main pipe run |
| V | 1 Depth to invert not exceeding 2 metres |
| | 2 Depth to invert exceeding 2 metres but not exceeding 3 metres and so on in steps of 1 metre |
- Lateral connections** **16** The items for lateral connections shall in accordance with the Preambles to Bill of Quantities General Directions include for:
- Item Coverage**
- (a) excavation of acceptable material (CC-RMP-00600 paragraphs 17 and 18);
 - (b) excavation of unacceptable material (CC-RMP-00600 paragraph 19);
 - (c) excavation of hard material (CC-RMP-00600 paragraph 23);
 - (d) locating and making entry;
 - (e) breaking up beds, haunches and surrounds;
 - (f) disconnection from existing pipe to be replaced;
 - (g) dealing with existing flows;
 - (h) backfilling and compaction;
 - (i) disposal of material (CC-RMP-00600 paragraph 39);
 - (j) pipes, fittings and saddles;
 - (k) bedding, haunching and surrounding;
 - (l) relaying or replacing existing pipes disturbed or broken;
 - (m) excavation in contaminated land and disposal of all contaminated materials including clothing, wash water and any other materials to a licensed site;
 - (n) sealing off disused ends;
 - (o) relaying or replacing existing pipes disturbed or broken, including cutting, jointing and fittings;
 - (p) cleaning, clearing obstructions and testing including all CCTV surveys and inspections;
 - (q) photographs;
 - (r) testing.

2. References

2.1 TII Publications (Standards) References


CC-RMP-00010 Introduction to the Requirements for Measuring and Pricing

CC-RMP-00500 Requirements for Measuring and Pricing of Drainage and Service Ducts

CC-RMP-00600 Requirements for Measuring and Pricing of Earthworks

CC-RMP-01900 Requirements for Measuring and Pricing of Protection of Steelwork against Corrosion



 Ionad Ghnó Gheata na Páirce,
Stráid Gheata na Páirce,
Baile Átha Cliath 8, D08 DK10, Éire

 Parkgate Business Centre,
Parkgate Street,
Dublin 8, D08 DK10, Ireland

 www.tii.ie

 info@tii.ie

 +353 (01) 646 3600

 +353 (01) 646 3601