



NOTES :

1. DO NOT SCALE.
2. ALL ITEMS SHOWN MAY NOT BE REQUIRED ON AN INDIVIDUAL PROJECT. ONLY ITEMS INCLUDED ON THE CONTRACT DRAWINGS AND SCHEDULES, AND ANY ADDITIONAL ITEMS THEREIN, ARE TO BE PROVIDED.
3. SAFETY FENCE HAS NOT BEEN INCLUDED IN THE VERGE. REQUIREMENTS FOR SIGHT DISTANCE AND THE SET-BACK AND CLEARANCES FOR SAFETY FENCES IN ACCORDANCE WITH TD 19, MUST BE PROVIDED WHERE SAFETY FENCE IS INCLUDED.
4. THE LIGHTING COLUMN FOUNDATION SHOWN IS ILLUSTRATIVE ONLY.
5. PIPES SHALL BE LAID TO THE LEVELS SHOWN ON THE DRAWINGS AND SCHEDULES.
6. DRAINAGE ALONG THE TOP OF THE EMBANKMENT SHALL BE AS SHOWN ON THE DRAWINGS AND SCHEDULES.
7. A TYPICAL SERVICES LAYOUT AND REQUIREMENTS FOR CLEARANCES AND COVER ARE SHOWN ON RCD/2700/50.
8. LONGITUDINAL LAND DRAINS TO BE PROVIDED WHERE REQUIRED THESE DRAINS ARE TO BE CONNECTED INTO THE SURFACE WATER SYSTEM